

Purchasing Division

ADDENDUM NO. 1

DATE: March 22, 2017

FROM: City of Grand Junction Purchasing Division

TO: All Offerors

RE: Las Colonias Park Slough Restoration, Erosion Control Blanket, Topsoil, and

Seeding IFB-4356-17-DH

Offerors responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded and supplemented as to this date as hereinafter described.

Please make note of the following clarifications:

- 1. Q. The quantity of Topsoil Cubic Yardage in the bid documents specifies a 3" depth over the erosion control blanket area. The quantity specified of 120 CY does not correlate with any of the specified blanket quantity coverage areas. Can you please confirm that the topsoil quality is correct?
 - A. See attached Revised Bid Schedule with corrections. Contractor shall utilize the attached Revised Bid Schedule with their bid submission.

The original solicitation for the project noted above is amended as noted.

All other conditions of subject remain the same.

Respectfully,

Duane Hoff Jr., Senior Buyer City of Grand Junction, Colorado

REVISED - Addendum 1 PROJECT: Las Colonias Slough Restoration **Erosion Control Blanket Installation**

Bid Tab

Bid Item No.	<u>Description</u>	Quantity	Units	Unit Price	Total Price	Notes / Assumptions
	Site Preparation					
1	Mobilization/Demobilization/Bonding/Insurance	1	LS			
2	Trail/Pedestrian signage	1	LS			Install signage on bike path to inform and divert pedestrian traffic
				Sub Total:		
	Care of Water					
3	General Staging Area BMPs	1	LS			Covers any aggregate material required for haul roads
4	Care of Water Practices	1	LS			Block flow at inlet structure prior to construction
				Sub Total:		
	Erosion Control Blanket, Topsoil, and Seeding					
5	Furnish and Install Erosion Control Blanket Type 1	2,440	SY			Nedia KoirMat 700 or approved equivalent
6	Furnish and Install Erosion Control Blanket Type 2	5,770	SY			Erosion Control Blanket C32 BD or approved equivalent
7	Furnish and Grade Topsoil	120	CY			Assumes 1"-4" thick over erosion control blanket type 1 area. Volume assume 2/3rds of this area - only install on areas of bank with exposed fine soil
8	Furnish and insta ll riparian native seed mix	30	LB			Broadcast over upper 2/3 rds of bank, concentrate in areas of exposed soil
9	Furnish and insta ll wetland native seed mix	7	LB			Broadcast over lower 1/3 rd of bank, concentrate in areas of exposed soil
				Sub Total:		
	TOTAL LUMP SUM BID					