



Purchasing Division

## **ADDENDUM NO. 2**

**DATE: June 11, 2019**  
**FROM: City of Grand Junction Purchasing Division**  
**TO: All Offerors**  
**RE: 2018 Safe Routes to School – Bookcliff Middle School IFB-4655-19-DH**

Offerors responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded and supplemented as to this date as hereinafter described.

Please make note of the following clarifications:

### 1. **SP-6 UTILITIES**

Known utilities within the limits of this project are:

Ute Water  
Fruitvale Irrigation District 180-185  
Xcel Energy (Gas and Electric)  
City of Grand Junction Sanitary Sewer

The work described in these plans and specifications requires coordination between the Contractor and the utility companies in conducting their respective operations as necessary to complete the utility work with minimum delay to the project.

The work listed below shall be performed by the Contractor in accordance with the plans and specifications, and as directed by the Engineer. The Contractor shall keep each utility company advised of any work being done to its facility, so that the utility company can coordinate its inspections for final acceptance of the work with the Engineer.

FOR:  
Ute Water – Justin Bates – 970-242-7491  
Fruitvale Irrigation District 180-185 – Jerry Myers – 970-201-6454  
Xcel Energy (Electric) – Steve Piburn – 970-244-2664  
Xcel Energy (Gas) – Sarah Darricau – 970-244-2656  
City of Grand Junction Sanitary Sewer – Lee Cooper – 970-256-4155

The work listed below will be performed by the utility owners or their agents:

- Fire Hydrant – Ute Water will perform tests on the fire hydrant after its relocation by the contractor and prior to acceptance.
- Irrigation Manhole – Fruitvale Irrigation will shut off water for up to two days for contractor to install the connection between the 15-inch RCP and 14-inch PVC.

GENERAL:

The Contractor shall comply with Article 1.5 of Title 9, CRS ("Excavation Requirements") when excavation or grading is planned in the area of underground utility facilities. The Contractor shall notify all affected utilities at least two (2) business days, not including the day of notification, prior to commencing such operations. The Contractor shall contact the Utility Notification Center of Colorado (UNCC) at (8-1-1) or 1-800-922-1987 to have locations of UNCC registered lines marked by member companies. All other underground facilities shall be located by contacting the respective company. Utility service laterals shall also be located prior to beginning excavating or grading.

The location of utility facilities as shown on the plan and profile sheets, and herein described, were obtained from the best available information.

All costs incidental to the foregoing requirements will not be paid for separately but shall be included in the work.

The original solicitation for the project noted above is amended as noted.

All other conditions of subject remain the same.

Respectfully,

A handwritten signature in black ink, appearing to read "Duane Hoff Jr.", written in a cursive style.

Duane Hoff Jr., Senior Buyer  
City of Grand Junction, Colorado