

Purchasing Division

ADDENDUM NO. 2

DATE: November 2, 2022

FROM: City of Grand Junction Purchasing Division

TO: All Offerors

RE: WWTP Improvements & Asset Replacement IFB-5131-22-KH

Offerors responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded and supplemented as to this date as hereinafter described.

Please make note of the following clarifications:

1. Q: Want to confirm there are no required ADA compliant parking spots?

A: There are no ADA compliant spots required.

2. **Q:** Is the Concrete pavement specification Class P?

A: Concrete shall conform to the requirements for Class P.

3. **Q:** Is there a specification or suggested manufacturer for the concrete curb stops. What length 6',7', or 8'. Natural gray or painted yellow.

A: Concrete curb stops shall be precast 6' natural gray. We do not have a specification or suggested manufacturer for the product.

- 4. Q: Are the thermoplastic lines inlaid, what mil thickness for the lines?
 - **A:** An amendment has been made to the Bid Schedule to change the parking lot striping from thermoplastic lines to Pavement Marking Paint.
- 5. **Q:** Can the landscape restoration and asphalt patching (no bid item) be completed after the scheduled completion date when weather allows for these items to be properly completed?
 - A: Landscape restoration and asphalt patching may occur no later than April 30th, 2023.
- 6. The address listed in Question 9, from Addendum 1, should be corrected to state "251 27 Road".
- 7. The bid schedule has been updated to include Hot Mix Asphalt for asphalt patching and the changes from Addendum 1.
- 8. Final Completion has been amended to April 30th, 2023.

The original solicitation for the project noted above is amended as noted.

All other conditions of subject remain the same.

Respectfully,

Kassy Hackett, Buyer

City of Grand Junction, Colorado

Bid Schedule: WWTP Improvements & Asset Replacement (Addendum 2)

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Total Price
1	202	Removal of Concrete (Includes unclassified excavation)	164.	SY _		
2	202	Removal of Asphalt Mat (Includes unclassified excavation)	732.	SY		
3	202	Removal of Fence	31.			
4	202	Removal of Bollard	2.			
5	202	Concrete Washout Facility	1.			
6	208	Reset Gate	1.			
7	210	Reset Chain Link Fence (6')	237.			
8	210	Reset Landscape Ground Cover (Includes sprinkler system)	1.			
9	210	Aggregate Base Course (Class 6) (6" Thick)	42.	CY _		
10	304	Reconditioning (12" Deep)	83.	SY _		
11	401	Hot Bituminous Pavement (Patching) (4" Thick) (Grading SX, PG 64-22) (GYR.=75)(Two 2" Lifts)	50.	SY _		
12	406	Concrete Pavement (8")	1,360.	SY _		
13	412	Concrete Sidewalk (4")	16.	SY _		
14	608	Concrete Curb Stop	14.	EACH		
15	627	Pavement Marking Paint (4" White Solid)	278.	. –		
16	627	Fence Chain Link (6')	136.	LF _		
17	607	Privacy Fance Slats (Beige)	361.	LF _		
18	607	Mororized Gate (Includes electrical wiring, motor, fire department access box, 24 remotes, and keypad entry for existing 25'	1.	LS _		
19	607	Gate (4' x 6')	1.	EACH_		
20	607	Gate (12' x 6')	1.			
21	607	1 1/4" Electrical Conduit	189.	. –		
22	613	Sanitary Facility	1.			
23	620	Construction Surveying (Includes As-Built Drawings)	1.			
23	625	Mobilization	1.	LS		
24	626	Traffic Control (Complete in Place)	1.	LS		
МС		Minor Contract Revisions				\$ 15,000.00
R			Bid An	nount:	\$_	
	Bid Am	ount:				dollars